



Addendum #1

4400 N. Big Spring, Suite 203, Midland, TX 79705

Ph. 432.686.8001 Fax 432.683.3487

Date: **4.17.18**
Project: **MSU Quad Landscape**

Item:

- 1 Contractors shall submit a schedule to complete the project with their bid. If there are savings for increasing/decreasing the schedule, the contractor shall identify these savings with their bid. If no schedule is submitted, the contractor will be obligated to follow the schedule listed in the RFP.
- 2 Separate contracts for the HS+HS Exterior and the Quad Landscaping may be issued if the best value is not obtained by selecting a single contractor for both projects. If there is a deduct for both contracts to be issued to the same contractor, this deduct should be submitted with the contractor's bid.
- 3 Section 1.3.B of spec 01010 specifies personal protective equipment all personnel must wear while they are on the HS+HS construction site, which is under Trinity Hughes/Sundt's responsibility. Gloves shall be worn at all times, in addition to the other items listed.
- 4 Contractor is responsible for all aspects of maintaining a safe work site, including the installation of temporary fencing around the perimeter of the construction zone. Bidders shall include pricing for the installation of 6' tall chain link temporary fencing around the entire construction zone. It is not necessary to duplicate the fencing Trinity Hughes/Sundt has already installed on the west side of the Quad construction zone.
- 5 Detail 01 of the Quad Landscape drawings includes signage lettering and a brief description to match the lettering on the Taft/Hampstead monument signs. As a further description, the lettering shall be 8" cast aluminum in "Profile" font, stud mounted, and dark bronze anodized finish (TNT Signs has supplied to MSU in the past, although equivalents are acceptable).
- 6 Trash receptacles in the specs identify model A-24 and the drawings show A-36. Use the A-36 (36 gallon) trash cans.
- 7 All site amenities such as tables, benches, and chairs are to be surface mounted with anchor bolts.
- 8 Water source connection for the irrigation is shown on the upper left side of sheet L-4.1.
- 9 A 5% bid bond will be required if awarded this project.
- 10 P&P Bonds will be required if awarded the project.
- 11 All questions are due to Steve Shelley in Purchasing by noon on Monday, 4/23/18